



Ref. No. : ML/ 20250911

Date: 11th SEPT 2025

Manjeet Lochab, HL City , Bahadurgarh

Dear Sir,

Subject : Quotation For 5 KW On Grid Solar Power Plant (Waaree)

1. System Specifications

Component	Details	Qty
Solar Panels	Waaree 595W N Type TOPCON (Bi Facial) A Grade (25 year warrenty)	9 (5355 Watt)
Inverter	Waaree Brand 6 kW Ongrid Inverter (8 year warrenty)	1
Mounting Structure	Galvanized Iron (GI) for Rooftop	As per req.
DC Cables & Connectors	4mm ² /6mm ² PV Cable, MC4 Connectors	As per req.
AC/DC Distribution Box	Equivalent with SPD & MCBs 600Vdc + 3 phase	1 set
Earthing & Lightning Arrestor	Copper-bonded rod & LA Kit + Earthing 3 pcs	1 set
Net Metering	Bi-directional meter (provided by DISCOM)	1
Installation & Labour	Civil works, commissioning	-
Transportation & Logistics	-	-
GST (12-18%)	-	-
Total System Cost	-	205000

(Note: Prices are indicative; final costs may vary based on site conditions.)



2. Scope of Work (Vendor Responsibility)

Design & Engineering

Site assessment & shadow analysis

System design & load calculation

Supply of Materials

High-efficiency Waaree solar panels

Waaree grid-tied Ongrid inverter with warranty

Mounting structure, cables, and accessories

Installation & Commissioning

Mounting structure fabrication & installation

Panel fixing, wiring, and inverter setup

Earthing & lightning protection

Grid synchronization & testing

Net Metering Approval

Assistance in DISCOM application

Coordination for meter installation

Warranty & AMC

Solar Panels: 25 years performance warranty

Inverter: 8 years manufacturer warranty

3 year free maintenance support

3. Client Responsibilities

- ✓ Provide necessary roof space (approx. 300–350 sq. ft.)
- ✓ Obtain necessary permissions (if required)
- ✓ Ensure grid availability & net metering approval support
- ✓ Provide electricity bills & necessary documents for DISCOM process
- ✓ Clear payment as per agreed terms



Skyline Stores

+91 99911
skyline-st
Shop No. 8
Kaimri Road,

4. Payment Terms

Advance: 40% at the time of booking

On Delivery of Material: 40%

After Commissioning: 20%

5. Expected Timeline

Material Procurement: 7–10 days

Installation & Commissioning: 5–7 days

Net Metering Activation: 15–30 days (depends on DISCOM)

6. System Performance Estimates

Annual Generation: ~10500-11000 units

Savings: ₹80–90 Thousand/year (depends on tariff)

ROI Period: 2.5-3 years(Aprox)

7. Terms & Conditions

Prices valid for [7–10 days]

Warranty as per manufacturer terms

Any additional civil work will be charged extra

Force majeure clauses apply

For any queries, please contact:

Skyline Stores

Cont : 7876555555/9991144903

Signature: _____

Authorized Representative